BRUHAT BANGALORE MAHANAGARA PALIKE
DASARAHALLI ZONE
Office of the Executive Engineer Dasarahalli Division
SCHDULE-B

Name Of Work: Comprehensive Development of Works in Ward No 14

Job Code: 014-18-000057

Sl	Description of Work	Unit	Qty	Sanctioned Rates	
				In figures (Rs)	In Words (Rs)
1	KSRRB 300-2. Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as	Cum	642.35		
2	KSRRB 300-Compaction KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications. MORTH / Chapter	Sqm	809.25		
3	KSRRB M400- Wet Mix Macadam KSRRB M400-17. Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications.	Cum	494.04		
4	KSRRB M500-6. Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications. MORTH Specification No. 502 (P.No.158 I.No.21.6)Issue Basic Rate Date:02.11.2021 to till now	Sqm	3293.57		
5	KSRRB 500-2. Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH specification clause 501 (P.No.158 I.No.21.2)	Sqm	4723.71		
6	KSRRB 500-7. Providing and applying tack coat using 80/100 grade bitumen(VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH/Chapter 5	Sqm	4723.71		

7	KSRRB M500-17. Providing and laying dense graded bituminous macadam using crushed aggregates of specified grading, premixed with VG30 grade bituminous binder and, transporting the hot mix to work site, laying to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH table 500-10 complete in all respects complete as per specifications.. MORTH Specification No. 507 - using 40/60 TPH capacity H.M.P. with Mechanical paver Gr-II (50 mm to 75 mm) with	Cum	164.68		
8	KSRRB M500-19. Providing and laying bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 509 complete in all respects complete as per specifications. - using40/60 TPH capacity H.M.P. with Mechanical Paver Gr-II (30 mm to 45 mm) with 6 % CRMB 55	Cum	141.71		
9	KSRRB M800-13.Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface:- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803	Sqm	157.09		

Signature of the Contractor

Executive Engineer
Dasarahalli Division

ಕಂಡಿಕೆ( )ರಲ್ಲಿ ವಿವರಿಸಿರುವ ಅಂಶಗಳ ಬಗ್ಗೆ
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು( )ರವರು
ದೃಢೀಕರಿಸಿಕೊಳ್ಳುವ ಷರತ್ತಿಗ ಒಳಪಡಿಸಿ ಡಿ.ಟಿ.ಎಸ್
ಅನುಮೋದಿಸಿದೆ.
ಕರಡು ಟೆಂಡರ್ ಷೆಡ್ಯೂಲ್‌ನ್ನು ತಿದ್ದುಪಡಿ ಮಾಡದಂತೆ
ತಿದ್ದುಪಡಿ ಇಲ್ಲದೆ ಅನುಮೋದನೆ ನೀಡಲಗಿದೆ.
ತಿದ್ದುಪಡಿಗಳ ಒಟ್ಟು ಸಂಖ್ಯೆ:.....nill.....
ರದ್ದುಗೊಳಿಸಿರುವ ಒಟ್ಟು ಐಟಂಗಳ ಸಂಖ್ಯೆ...nill.....

ಮುಖ್ಯ ಅಭಿಯಂತರರು (ದಾಸರಹಳ್ಳಿ)